



DELHI STATE CANCER INSTITUTES

- centres par excellence in the service of humanity
(A group of autonomous institutions under the Govt. of NCT of Delhi)

EAST: DILSHAD GARDEN, DELHI 110095

EPABX: +91-11-2213 5200, 2213 5700 FAX: +91-11-2211 0505

WEST: C-2/B, JANAK PURI, NEW DELHI 110058

EPABX: +91-11-2550 1111, 2554 1111 FAX: +91-11-2554 9999

Website: www.dsci.nic.in E-mail: director.dsci@nic.in



NOTICE INVITING QUOTATION

DSCI-H012(12)/24/2016-ENGG-CIVIL(DSCI)

Dated: 20/12/17

Sealed Item rate quotations are invited on behalf of Director, DSCI from CPWD (Civil) registered contractors of appropriate class, so as to reach the undersigned on or before **27/12/17** upto 3:00 P.M as per schedule of quantities and terms & conditions given below. The received quotations shall be opened on the same day at 3:30 P.M

Name of Work - Replacement of damaged veneer wall paneling in Director room at Delhi State Cancer Institute (East) Dilshad Garden Delhi

Estimated Cost: Rs. 1,06,720/-

Terms and conditions:-

1. Time allowed is 07 days.
2. Agency has to deposit EMD of Rs.2,134/- in the form of Demand Draft/FDR of schedule bank issued in favour of Delhi State Cancer Institute alongwith quotation.
3. Quotation will be issued from the office of Executive Engineer(C) only to the eligible quotationers who will submit the required documents as per terms & conditions of NIQ alongwith application on **26/12/17** upto 4:00 P.M.
4. Institute reserves the right to reject the quotation without assigning any reasons.
5. Contractor has to carry out the work as per programme given by Engineer In charge.
6. Sample shall be got approved before execution.
7. Rates to be quoted by the bidder are exclusive of GST.
8. GST as applicable will be paid extra.
9. **Quotationers will have to submit following documents alongwith quotation:**
 - (a) **Self attested copy of GST Registration certificate.**
 - (b) **Self attested copy of PAN card.**
 - (c) **Self attested copy of CPWD (civil) registration certificate**
6. Agency has to carry out the work as per programme given by Engineer In charge.
7. Contractor has to produce computerized measurement & bills for verification & payment.
8. Necessary recoveries shall be made from agency as per statutory norms.
9. No T & P shall be issued by the Institute.

10. Agency shall be responsible for watch and ward of materials till it is completed and handed over to DSCI.
11. Payment will be made after successful completion of work.
12. A penalty of Rs.200/- per day will be imposed for delay beyond the prescribed time of 07 days to be recovered from bill.
13. Since, it is a working hospital, the agency shall carry out the work as per time schedule given by Engineer in charge which might be beyond hospital timing.
14. EMD will be released after successful completion of work.
15. NIQ is available on website www.dsci.nic.in
16. Downloaded quotations shall not be entertained.



**Executive Engineer (C)
DSCI**

Name of Work - Replacement of damaged veneer wall paneling in Director room at Delhi State Cancer Institute (East) Dilshad Garden Delhi

Sl. No	Description	Qty.	Unit	Rate	Amount
1	Dismantling wooden boardings/veneer work in lining of walls and partitions, including removing rubber based adhesive from the existing frame work including disposal of unused materials outside the DSCI campus.	100.00	sq. feet		
2	Providing & fixing 12 mm thick Water proof ply of approved make (Centaury/DUCO/Greenlam) with nails & adhesive to existing frame work etc. complete & as per direction of engineer in charge	100.00	sq. feet		
3	Providing & fixing 4 mm thick Water proof one side decorative veneer ply Santos dark shade of approved make (Centuary/DUCO/Greenlam) to expose face with nails & adhesive to existing ply wood surface etc. complete & as per direction of engineer in charge	60.00	sq. feet		
4	Providing & fixing 4 mm thick Water proof one side decorative veneer ply Red Sadar light shade of approved make (Centuary /DUCO/ Greenlam) to expose face with nails & adhesive to existing ply wood surface etc. complete & as per direction of engineer in charge	45.00	sq. feet		
5	Providing & fixing 12x12 mm corner gola of 1st class teak wood to expose face with nails & adhesive etc. complete & as per direction of engineer in charge	26.00	RFT		
6	Polishing with high gloss PU polishing on new work (Two or more coats) including a coat of wood filler etc. complete & as per direction of engineer in charge	100.00	sq. feet		
7	Polishing with high gloss PU polishing on old work (one or more coats) including a coat of wood filler etc. complete & as per direction of engineer in charge	100.00	sq. feet		
Total Amount					

**Executive Engineer (C)
DSCI**