



## DELHI STATE CANCER INSTITUTES

- centres par excellence in the service of humanity

(A group of autonomous institutions under the Govt. of NCT of Delhi)

**EAST: DILSHAD GARDEN, DELHI 110095**

EPABX: +91-11-2213 5200, 2213 5700 FAX: +91-11-2211 0505

**WEST: C-2/B, JANAK PURI, NEW DELHI 110058**

EPABX: +91-11-2550 1111, 2554 1111 FAX: +91-11-2554 9999

Website: [www.dsci.nic.in](http://www.dsci.nic.in) E-mail: [director.dsci@nic.in](mailto:director.dsci@nic.in) NIN No: 1112313380



### NOTICE INVITING QUOTATION

DSCI-H012(11)/2/2023-Engg-Civil(DSCI)/163

Date: 27/02/2023

Sealed item rate quotations are invited on the behalf of the Director, DSCI from CPWD registered contractor in composite category so as to each the undersigned on or before 08/03/2023 at 3:00 P.M as per schedule of quantities and terms & conditions given below. The quotations shall be opened on the same day at 3:30 P.M

**Name of Work: Misc repair work at various locations at Delhi State Cancer Institute (East), Dilshad Garden, Delhi**

**Estimated Cost: Rs. 1,98,745/-**

#### Terms & Conditions:-

1. Time allowed for work is 15 days.
2. Agency has to deposit EMD of Rs.4,000/- in the form of Demand Draft/FDR of schedule bank issued in favour of Delhi State Cancer Institute alongwith quotation.
3. Quotation will be issued from the office of Executive Engineer(C) only to the eligible quotationers who will submit the required documents as per terms & conditions of NIQ alongwith application by **07/03/2023** upto 04:00 P.M OR can be downloaded from DSCI website.
4. The Quotation must be in sealed cover addressed to EE, DSCI Delhi
5. Deptt reserves the right to reject the quotation without assigning any reasons.
6. Contractor has to carry out the work as per programme given by Engineer In charge.
7. Samples shall be got approved by Engineer in charge before execution.
8. Contractor shall be responsible for watch and ward of materials.
9. Site shall be cleared after completion of work.
10. Quoted rates are inclusive of all taxes. Nothing extra shall be paid on any a/c.
11. Contractor has to produce computerized measurement & bills for verification & payment.
12. The quotationers will have to submit the qualification/eligible bid containing the following:-
  - i. **Duly signed copy of GST Registration Certificate.**
  - ii. **Duly signed copy of latest GST return.**
  - iii. **Duly signed copy of CPWD registration certificate of composite category.**
  - iv. **Duly signed copy of PAN card.**
  - v. **Duly signed copy of filled schedule of qty.**

13. EMD will be released after successful completion of work.

14. NIQ is available on website: [www.dsci.nic.in](http://www.dsci.nic.in) & Notice board.

**Executive Engineer(C)**  
**DSCI**

**Name of Work: Misc repair work at various locations at Delhi State Cancer Institute (East), Dilshad Garden, Delhi**

Item No.	Description of items	Qty	Unit	Rate	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in- charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.50	cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
2.1	1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size)	0.50	cum		
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground,c				
3.1	With cement mortar 1:4 (1cement: 4 coarse sand)	15.00	sqm		
4	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	15.00	sqm		
5	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete (A)Size of Tile 600x600 mm	2.00	Sqm		
6	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved	4.00	sqm		

## DSCI-H012(11)/2/2023-Engg-Civil(DSCI)

1236489/2023/Engineering(Civil)-DSCI

	make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.				
7	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building, all complete as per the architectural drawings, with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand), laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade, including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.				
7.1	Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	2.00	sqm		
8	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				
8.1	Granite of any colour and shade Area of slab over 0.50 sqm	2.00	sqm		
9	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	4.00	sqm		
10	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
10.1	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	100.00	kg		
11	Providing and fixing stainless steel ( Grade 304) railing made of Hollow tubes, channels, plates etc., including	50.00	kg		

## DSCI-H012(11)/2/2023-Engg-Civil(DSCI)

1236489/2023/Engineering(Civil)-DSCI

	welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).				
12	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
12.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	425.00	sqm		
13	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
13.1	One or more coats on old work	50.00	sqm		
14	Finishing walls with Acrylic Smooth exterior paint of required shade :				
14.1	Old work (One or more coat applied @ 0.90 ltr/10 sqm).	70.00	Sqm		
15	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:				
15.1	One or more coats on old work	70.00	sqm		
16	Repairing of existing polycarbonate dome up to 1.25 mtr dia by engaging specialized worker including all required material i.e fiber, resin and chemical etc and cost of skilled labour, T & P all complete as per direction of Engineer-in-Charge.	2.00	each		
17	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all loads including all lifts involved	5.00	cum		
<b>Total</b>					

**Executive Engineer(C )  
DSCI**